

Unit Heater Installation illustration.

Actual installation may vary.

First check structural strength of rafters to be sure they are capable of carrying the weight of the unit and related installation materials.

Angle iron size is based on a rafter span of 2' on center. If the rafter span is greater than 2' on center heavier angles may be required.

